Local Shielding around the Dummy Septum15

Sanja Damjanovic, DGS-RP

CERN, May 30, 2013

S. Damjanovic, CERN

1

FLUKA Geometry of the Local Shielding in SS15 as of April 2013



Soil, Stainless Steel, Marble, Aluminum, Concrete, Air





S. Damjanovic, CERN

Local Shielding around the Dummy Septum - New Proposal May 2013



R.F. Ortega

- lateral dimension:
 200 cm
- longitudinal dimension:
 100 cm
- vertical dimension:
 220 cm

FLUKA Geometry of the Local Shielding in SS15 as of May 2013



Soil, Stainless Steel, Marble, Aluminum, Concrete, Air



Residual Dose Rates with local shielding in SS15

1000

100

10

0.1

0,01

0,001

0,000

1e-05 🗎

two shielding designs -



2-dim projections in x-y plane, averaged over Δz =110cm (-1190<z<-1080cm, middle of SS15) and over ±30 cm in x, around the beam level



Comparing the color codes, the residual dose rates outside the local shielding similar for the two different shielding designs

S. Damjanovic, CERN

z-beam direction, x-vertical, y-horizontal direction

Residual Dose Rates with local shielding in SS15 - two shielding designs -

1 dim projections along y (horizontal) at the beam level, averaged over Δz =110 cm (-1190<z<-1080cm, middle of SS15)



Residual dose rates the same for the two different shielding designs throughout

1 & 2, REPLACEMENT OF	Specialist	Time and distance	Comments
COMPLETE SYSTEM			as of Nove
Venting of sector	TE-VSC	10 mins, remote intervention	rember 2012
Dismantling of shielding	EN-HE-HH	1 hour, distance >1m	3 persons, 1h/person
Disconnection of upstream and downstream flanges	TE-VSC	5 mins, contact	2 persons, 2.5min/person
Disconnect cabling, compressed air, water cooling, etc	TE-ABT, BE-BI, TE- VSC	10 mins, distance -contact	2 persons, 2.5min/person 1 person (TE-VSC), 5min/person
Removal of tank assembly	TE-ABT, EN-HE-HH	10 mins, distance 1m 2 persons, 2min/person – contact, 8min/person - 1m	Includes removal of support locking mechanisms
Installation of spare	TE-ABT, EN-HE-HH	15 mins, contact	This spare is non radioactive 3 persons, 5min/person
Reconnection of flanges	TE-VSC	10-15 mins	2 persons, 7.5min/person
Reconnection of cables, air, and water cooling.	TE-ABT BE-BI TE-VSC	10 mins	3 persons, 10min/person
Leak test	TE-VSC	30 mins	1 person, 30min/person
Installation of shielding	EN-HE-HH	1 hour	3 persons, 1h/person
Testing			

Updated information on intervention processes and duration required

Intervention - Disconnection of the downstream flange - results for the two shielding designs -



- 1) 0.8mSv/hx2.5min = 0.03 mSv
- 2) 0.6mSv/hx2.5min = 0.025 mSv

3) 0.4mSv/h×2.5min = 0.017 mSv